




INFRASET


THE AVENG GROUP



Terrace Blok® TB 300 TB 500



SABS
ISO 9001



Terrace Blok®

TB 300
TB 500

The photographs in this brochure do not necessarily reflect actual product colours.

The INFRASET Terrace Blok® system has unique features that firmly establish it as a market leader.

Economical - 8 blocks per square metre.

Open or Closed Face Options - by using a unique patented slider system that fits easily between the blocks.






Plantability - its open back design and trough shape create a greenhouse effect within the environs of the block. This promotes rapid healthy plant growth with unrestricted root systems that aid in the stabilisation of the bank.

Quality - this product is manufactured under ISO 9002 requirements and carries a full manufacturers warranty.

Testing - backed by full-scale tests conducted by independent geotechnical engineers, every aspect of Terrace Blok® has been checked to establish the design integrity of the system.

Cautionary Note:

- The design of dry stack concrete retaining systems involves geotechnical rather than structural elements.
- Check with your local authorities regarding their requirements for the design, plan submission and stability certification of your retaining structure before commencing construction.
- This leaflet serves as a guideline not a guarantee. For specific applications please make use of our technical service.



Technical Data	TB 300	TB 500
Mass per block	32kg	48kg
Length	325mm	500mm
Width	390mm	390mm
Height	180mm	180mm
Number of blocks per m ²		
- Straight line	8	8
- Curved structures	9-10	9-10
Standard wall angle	70°	70°
Engineered options	55°-90°	55°-90°

GAUTENG (Sales Office)
Samrand Avenue West, Centurion, 0157
PO Box 45, The Reeds, 0061
Tel +27 (0)12 652-0000
Fax +27 (0)12 652-0132
Email infrasetinfo@infraset.com

KWAZULU-NATAL (Sales Office)
Off Nandi Drive (North), Effingham, 4061
PO Box 40313, Redhill, 4071
Tel +27 (0)31 569 6900
Fax +27 (0)31 569 6903
Email infrasetinfo@infraset.com



www.infraset.com